



LINE PLANTATION WORK ALONG ROAD

Roadside Avenue Plantation Project | Tehsil-Level Development



PROJECT HIGHLIGHTS

- Continuous plantation on both sides of the road
- Green corridor development with orderly tree rows
- Road landscape improvement and long-term shade corridor



PROJECT NEED

Why roadside line plantation is required



PROJECT HIGHLIGHTS

- Develop a continuous green corridor along the project road
- Improve visual quality and roadside environment
- Reduce dust, glare, heat and roadside noise
- Provide shade and improve comfort for road users
- Support soil protection and landscape improvement

PROJECT OBJECTIVES

Key objectives of the plantation programme



PROJECT HIGHLIGHTS

- Plant trees in straight, uniform lines on both road sides
- Create a safe and attractive avenue plantation
- Use suitable species according to soil and site conditions
- Ensure high survival through protection and watering
- Establish a sustainable roadside green belt

SITE SURVEY & PLANNING

Pre-plantation survey and corridor assessment



PROJECT HIGHLIGHTS

- Road width, shoulder and available plantation strip
- Existing trees, utilities, drains, culverts and intersections
- Soil, drainage, water availability and local climate
- Identification of safe planting offsets from road edge
- Chainage-wise plantation planning and marking

LINE PLANTATION LAYOUT

Straight roadside plantation on both sides



PROJECT HIGHLIGHTS

- Continuous rows aligned with the road corridor
- Uniform spacing for a clean and planned appearance
- Planting offset maintained from the carriageway
- Staggered or multiple rows where sufficient land is available
- Open sight distance maintained at curves and junctions

SPECIES & PLANTING DESIGN

Selection of trees and planting pattern



PROJECT HIGHLIGHTS

- Select hardy, locally suitable and low-maintenance species
- Use flowering, shade and avenue trees according to location
- Healthy nursery-grown saplings with strong root systems
- Provide suitable pit size, soil mixture and organic manure
- Maintain consistent spacing and planting depth

PLANTATION IMPLEMENTATION

Execution methodology



PROJECT HIGHLIGHTS

- Site marking and pit excavation
- Soil preparation and planting of healthy saplings
- Tree guards / protection around young plants
- Initial watering and soil settlement
- Chainage-wise inspection and quality control

WATERING & PROTECTION

Ensuring establishment and survival



PROJECT HIGHLIGHTS

- Regular watering during establishment period
- Protection from traffic, grazing and accidental damage
- Replacement of dead or damaged saplings
- Weeding, mulching and soil loosening around plants
- Use of tanker or available irrigation source where required

MAINTENANCE & MONITORING

Long-term avenue plantation management



PROJECT HIGHLIGHTS

- Routine inspection of plantation stretches
- Pruning and removal of damaged branches when required
- Monitoring survival rate and plant health
- Repair and replacement of damaged tree guards
- Maintain a chainage-wise plantation register

EXPECTED OUTCOMES

A continuous green road corridor



PROJECT HIGHLIGHTS

- Beautiful and uniform tree-lined road environment
- Improved shade, dust control and roadside microclimate
- Better landscape value and visual identity of the corridor
- Improved soil protection and ecological value
- Long-term green infrastructure asset for the project area